


LINKAGES

- Type 1 - Greenway
- Type 2 - Thoroughfare Street
- Type 3 - Collector & Commercial Street
- Type 4 - Collector Parkway
- Type 5 - Parkway (U.S. 69 Corridor)
- Parkway (U.S. 69 Corridor) No Bike/Pedestrian Trail
- Adjacent Community / Private Linkage

- Key On-Street Bike Routes Providing Linkages (with parallel sidewalk for pedestrian access)
- Future Grade Separation
- Arboretum Entrance Corridor (Type 2 Greenway Linkage with Additional Landscape Amenities)
- Streams
- Railroads

LAND USE

- Public Park and Greenway Land (Existing)
- Public Park and Greenway Land (Proposed)
- Other Open Space (May include streamway corridors)  
General Location, Potential Public or Private Park or Open Space
- School  
General Location, Potential School Site
- Public/Semipublic Community Use Facility



This map is based partially or wholly on data from the Johnson County, Kansas AIMS program under a license agreement with the City of Overland Park. Any reproduction or distribution of this map is subject to the terms and limitations of that agreement.

The use of data contained herein, and products derived therefrom, for the purpose of solicitation to buy or sell any product, property, or service is strictly prohibited.

Inquiries should be directed towards the Planning and Development Services Department GIS Division  
8500 Santa Fe Dr  
Overland Park, Kansas 66212  
(913) 895-5217 Fax (913) 895-5013  
www.opkansas.org

GREENWAY LINKAGES PLAN



# GREENWAY LINKAGES PLAN

December 2019

## GOVERNING BODY

Carl Gerlach, Mayor  
Terry Happer Scheier,  
Council President  
Gina Burke  
Richard Collins  
Faris Farassati  
Logan Heley  
Jim Kite  
Paul Lyons  
Chris Newlin  
Curt Skoog  
Fred Spears  
John H. Thompson  
Dave White

## PLANNING COMMISSION

Thomas Robinett,  
Chairperson  
Rob Krewson,  
Vice-Chairperson  
Michael Flanagan  
David M. Hill  
George Lund  
Edward J. "Ned" Reitzes  
Kim Sorensen  
Kip Strauss  
Holly Streater-Schaefer  
Janie Thacker  
Steve Troester

Bill Ebel, City Manager

## PLANNING AND DEVELOPMENT SERVICES DEPARTMENT

Jack Messer, Director

## INVOLVED STAFF

Greg Ruether, Director, Parks Services  
Leslie Karr, Manager, Current Planning  
Erin Ollig, Senior Planner  
Tim FitzGibbons, GIS Analyst  
Parks Services Staff  
Current Planning Staff

## How can you use the Greenway Linkages Plan and Guidelines?

The Greenway Linkages Plan and Guidelines can be used to determine the location and identify the type or types of linkages proposed in or around an area.

The Governing Body and the Planning Commission use the Plan and the Guidelines in their review of all site development proposals in the City including platting of land, rezonings and special use permit applications.

The Plan and the Guidelines are also used to plan for the timing of bike/pedestrian trail construction through the City's Capital Improvements Program (CIP) which is reviewed annually. Other jurisdictions, including surrounding communities and the county, can use the plan to help in coordinating the development of their own greenway linkages and parkland acquisition and improvements.

## How will the Greenway Linkages Plan be developed?

The Greenway Linkages Plan will only be developed through the cooperation of a three-way partnership between the City, landowners, and developers. The affected landowners and developers along the proposed greenway linkage routes will sell or give land for a linkage to the City as depicted on the Greenway Linkages Plan. The City is committed to prepare the necessary general concept plan and the individual site plans, install the landscaping (when and where proposed), build the bike/pedestrian trails, and maintain the trails and landscape easements once they are completed.

## What is the process for acquiring individual linkages?

The general steps for acquiring, building and maintaining individual segments of the greenway linkages are:

First, the area shown for a greenway linkage is identified and incorporated in the site planning for a preliminary plat for a subdivision, preliminary plan (for a school, church, temple, or public building), rezoning, or special use permit proposal.

Third, the City prepares the landscape plan.

Fourth, the City builds all bike/pedestrian trails along the trail easements and installs plant materials and seed or sod turf as required on the site landscape plan.

Fifth, once the bike/pedestrian trail is built and the landscaping installed, the City maintains the trail and landscape easements.

## What is a Greenway Linkage?

A greenway linkage is defined as open space land set aside for public use that is in linear form. A greenway linkage provides a connection between two or more locations, following natural areas (running adjacent to a stream or the base of a bluff) or those developed by man (running adjacent to a street or fence line).

These linkages may vary in width and may be created by joining separate adjacent parcels of land or may be located in street rights-of-way. Greenway linkages may be used for bike/pedestrian trails, buffers between differing types or intensities of land uses, as a means to conserve areas of natural or historic value, or as an enhancement to a community's parks and roadways.

## What are the Greenway Linkages Plan and Guidelines?

The Greenway Linkages Plan and Guidelines are two separate documents. The Greenway Linkages Plan displays the ultimate system of greenway linkages proposed in the City. The Plan, a map which is included in the City's Comprehensive Plan, is revised annually and shows the types of linkages proposed and the various public and semipublic uses that are linked together.

The Guidelines, which are only reviewed periodically, are found in a separate document from the Comprehensive Plan. The Guidelines describe in text and show in a series of graphic illustrations the five


different types of greenway linkages that are proposed. More detailed explanations of the illustrations below can be found in the Greenway Linkages Guidelines.

The Greenway Linkages Plan was incorporated in the 1991 Comprehensive Plan and has been reviewed annually as part of the Comprehensive Plan since. The initial 1991 Greenway Linkages Plan was only for the area of the city south of 119th Street. Since that time, the Greenway Linkages Plan was expanded to include all of the area south of I-435. In 2006, the Greenway Linkages Plan was significantly expanded to include the entire city.

The Greenway Linkages Guidelines was adopted as a separate policy document by a joint Planning Commission and City Council Resolution (City Council Resolution No. 2349 and Planning Commission Resolution No. 55) in October 1991.

## Why do we have the Greenway Linkages Plan and Guidelines?


The Greenway Linkages Plan and Guidelines were developed for use in guiding the development of an extensive system of linear open spaces, most of which will have bike/pedestrian trails, that link public parks and recreation facilities with schools and residences.



TYPE 1 LINKAGE (GREENWAY) is a linear open space area set aside for public use that is wide enough to accommodate a paved bike/pedestrian trail, landscaped area, fencing or other screening measure, but with limited access from adjacent land uses.


These types of linkages are often segregated from street rights-of-way to form a separate alignment that require landowner/developer land dedication, or a granting of an easement. The width of the land dedication or easement will vary between 30 and 60 feet.

Type 1 linkages join with other types of greenway linkages and cross street rights-of-way by means of an overpass, underpass or at-grade crossing at controlled or marked intersections. No other amenities are provided aside from those required for the bike/pedestrian trail construction and maintenance, and the comfort and safety of the public using the trail.




TYPE 2 LINKAGE (THOROUGHFARE STREETS) is a linear area of land set aside for public bike/pedestrian trail development that is part of the existing thoroughfare street rights-of-way. These linkages do not require additional rights-of-way beyond those required by city standards.


In some cases, Type 2 linkages may require an additional utility easement of five to ten feet in width outside of the existing street right-of-way that will be identified as such. The easement will be incorporated into the site plan at the time of preliminary plat, preliminary development plan, rezoning, or special use permit approval.



TYPE 3 LINKAGE (COLLECTOR AND COMMERCIAL COLLECTOR STREETS) is similar to a Type 2 linkage but is developed within the rights-of-way of collector, and commercial collector streets. This type of linkage may also require an additional easement of five to ten feet in width to provide space for underground utilities and landscaping. Construction of a Type 3 linkage is at the expense of the developer, unless a tract of land is dedicated to the city. The bike/pedestrian path shall be constructed with concrete pavement.



TYPE 4 LINKAGE (COLLECTOR PARKWAY) is a combination of a Type 1 and a Type 3 linkage and is used when a more significant amount of landscaped area or screening is desired. This linkage requires a 60-foot street right-of-way and an additional 25-foot-wide tract dedicated as parkland to the city for the bike/pedestrian trail. In special or unique circumstances, the Parks Director or their designee may approve an alternate compliance from the 25-foot tract requirement at the time of preliminary plat, preliminary development plan, rezoning, or special use permit approval.



TYPE 5 LINKAGE (PARKWAY) is similar to a Type 1 linkage, Type 5 linkages run parallel to U.S. 69 Highway within a landscape easement of 100 feet in width. The bike/pedestrian trail and landscape easements are outside of the highway right-of-way on both sides of U.S. 69 Highway south of 123rd Street. In special or unique circumstances, the Parks Director or their designee may approve an alternate compliance from the 100-foot-wide easement at the time of preliminary plat, preliminary development plan, rezoning, or special use permit approval.