- General Notes:

 1. All traffic control devices and application thereof, shall comply with the latest edition of the Manual on Uniform Traffic Control Devices (M.U.T.C.D.), and the City of Overland Park "Traffic Control Handbook". All roadside hardware shall have been tested and approved per the National Cooperative Highway Research Program (N.C.H.R.P.) Report 350 or the American Association of State Highway and Transportation Officials (A.A.S.H.T.O.) Manual for Assessing Safety Hardware
- American Association of State Highway and Transportation Officials (A.A.S.H.T.O.) Manual for Assessing Safety Hardware (M.A.S.H.), as applicable.

 2. The traffic control requirements shown on the plans are minimum requirements only and do not attempt to address in depth the variety of situations that may occur once construction has started. In no way do the requirements shown on these plans relieve the Contractor of their responsibility for selecting the proper traffic control devices and implementation procedures that will assure the safety of the motorist, pedestrians, and workers at all times. Any additional quantities of traffic control devices necessary to complete the contract or as ordered to be installed by the Engineer shall be considered subsidiary to the contract lump sum bid price.

 3. The Contractor may develop their own Temporary Traffic Control (T.T.C.) plan and submit to the Engineer for approval to use on this project.

 4. The Contractor shall be responsible for maintaining all traffic control devices on an around the clock basis, whether or not work is actively being pursued. Any deficiencies noted shall be corrected immediately.

 5. Should the Contractor fail to enforce the traffic control plan or fail to clean, repair, replace or otherwise maintain the traffic control devices when directed to do so by the Engineer or their representative, the City may take one or more of the following actions:

- Employ another contractor to correct the deficiencies and deduct the cost from the project pay estimate.
- Suspend all pay estimates until deficiencies are corrected.

 Stop the work until deficiencies are corrected.

 Place the contractor in default.
- During all construction periods, the Contractor shall have at the jobsite all necessary traffic control devices (appropriate signs, arrow displays, channelizing devices, direction indicator barricades, etc.) to properly close at least one lane of traffic.
- Any personnel working as a flagger must carry the proper flagger certification per KDOT Flagger Handbook, latest 805 WORK ZONE TRAFFIC CONTROL & SAFETY 800–20 version. Properly equipped flaggers shall direct traffic as shown on the plans or as directed by the Engineer. Flaggers clothing and equipment shall conform to the latest edition of the M.U.T.C.D.
- M.U.T.C.D.

 8. Existing Stop, Yield, and Street Name signs shall be maintained during construction. Stop, Yield, and Street Name signs may be temporarily erected (no less than 7 feet vertical from grade) until they can be permanently installed. Any temporary Stop or Yield sign installation to be left in place overnight shall require prior approval from the Engineer.

 9. Existing signs that conflict with the temporary traffic control shall be covered or removed by the Contractor. The Contractor is responsible for removal, storage, and reinstallation of the signs and posts. Any damaged signs or posts shall be replaced at the Contractor's expense.

 10. Existing pavement markings that conflict with the temporary traffic control shall be covered temporarily, removed, or obliterated, as shown in the plans or as directed by the Engineer. If covered temporarily, removable, non-reflective, preformed tape that is approximately the same color as the pavement surface shall be used.

 11. All orange construction signs shall be fluorescent orange micro-encapsulated prismatic retro-reflective grade sheeting.

 12. All retro-reflective sheeting on barricades, vertical panels, conical delineators, drums, tubular markers, cones, and directional indicator barricades shall use Kansas Department of Transportation approved high intensity retro-reflective grade sheeting.

- grade sheeting. 13. All pavement markings shall be retro-reflective with the use of glass beads.
- 14. The Contractor shall provide as many barricades with appropriate warning lights as needed to effectively close or restrict all or a portion of the right—of—way as shown in the plans or as directed by the Engineer. Type III barricades shall be used at street closings at the point of closure and where new streets under construction connect to an existing street.
- used at street closings at the point of closure and where new streets under construction connect to an existing street.

 15. Detectable Pedestrian Barricades and/or Channelizers shall be used for all sidewalk closures or temporary sidewalk facilities. A sidewalk detour shall be provided when necessary or directed by the Engineer. When existing pedestrian facilities are disrupted, closed, or relocated, the temporary facilities shall be detectable and include accessibility features consistent with the feature present in the existing facility. A barrier that is detectable by a person with a visual disability traveling with the aid of a long cane shall be placed across the full width of the closed sidewalk.

 16. Appropriate warning lights shall be used at night on all barricades, unless otherwise specified.

 17. For merge taper channelization, direction indicator barricades shall be used for all long—term stationary traffic control installations. They may be used for intermediate—term, stationary, short—therm stationary, and short duration installations but are not required. Standard conical delineators may be used in place of direction indicator barricades as long as the traffic control setup is three days or less.

 18. For longitudinal channelization, drums, conical delineators, or vertical panels are acceptable devices. For work that occupies a location less than 8 hours, retro—reflective cones (28 inches min. height) may be used. Where space
- occupies a location less than 8 hours, retro-reflective cones (28 inches min. height) may be used. Where space restrictions do not allow for the use of other more visible devices, retro-reflective tubular markers (28 inches min. height) may be used.
- spacing between channelizing devices should be approximately equal in feet to the posted speed limit in
- miles per hour.

 20. Sign mounting height, measured vertically from the bottom of the sign to the top of the curb, shall be a minimum or 7 feet. Sign lateral offset, measured from the edge of the sign to the face of the curb, shall be a minimum of 2 feet.

 21. Construction signs that are to be in place for 3 days or less may be mounted on approved temporary supports. The mounting height for signs on temporary supports, measured vertically from the bottom of the sign to the traveled way, shall be a minimum of 1 foot above the adjacent pavement surface, with the exception of the Road Work Ahead sign

- shall be a minimum of 1 foot above the adjacent pavement surface, with the exception of the Road Work Ahead sign (W2O-1), which shall be a minimum of 7 feet above the adjacent pavement surface.

 22. Placement of advance work zone signing shall be based on the speed of the facility and the spacing indicated in the Advance Warning Sign Spacing Table.

 23. End Road Work signs (G2O-2) should be placed at the downstream end of the termination area. If the End Road Work sign (G2O-2) will be less than 1,000 feet from other construction improvements, it may be omitted.

 24. For road closures on a thoroughfare, a Changeable Message Sign shall be used to provide advance notices for all directions impacted by the closure. The message shall be displayed for a minimum of one week in advance of the closure.

 25. All messages to be displayed on Changeable Message Signs shall be approved by the Engineer in advance of sign deployment.
- deployment.

 26. Arrow boards shall be used at all lane closures on multilane streets. Preferred placement of the arrow display is at the
- 26. Arrow boards shall be used at all lane closures on mutulane streets. Preferred placement of the arrow display is at the start of the taper area.

 27. Traffic control devices shall be completely covered or removed when not in use.

 28. Any vertical pavement drop-off that exceeds 3 inches in depth and is located within 4 feet of an adjacent travel lane, shall require either a Curb Drop Off Ahead sign (OP TTC1) or Shoulder Drop Off sign (W8-17), as appropriate, spaced not less than 500 feet apart. Channelizing devices shall be placed at the edge of the drop-off. If the drop-off is to remain in place for more than 3 days, a solid edge line pavement marking shall be present for the adjacent lane.

 29. The minimum lane width for a thru lane is 10 feet. The minimum lane width for a turn lane is 10 feet. A lane shall be closed if the minimum lane width coract be maintained.
- closed if the minimum lane width cannot be maintained.

- 1. Construction shall be sequenced to provide the least possible adverse effect to residents, roadway users, and pedestrians.


 2. Construction materials shall be kept off sidewalks and consolidated in areas within the City right-of-way unless otherwise
- approved by the Engineer.


 Mud and construction debris on streets or sidewalks shall be cleaned off immediately.

 Access shall be maintained to all drives and side streets or as indicated in the Temporary Traffic Control plan.

- Plate Ahead warning sign (W8-24) with a Type B warning light shall be installed at the location of the street plate, or where the temporary road surface is left below the final surface elevation (unless an asphalt wedge is installed on the
- needing and training eages).


 10. Any construction activities which require the closing of a lane of traffic on thoroughfares (arterial streets) or collector streets shall not occur between the hours of 7:00 a.m. to 8:30 a.m. and 4:00 p.m. to 6:00 p.m. or on holidays or weekends, unless prior approval is received from the Engineer or there are emergency repairs necessary by a utility company or their representative.







- Adjacent sections shall have the same base color (orange, white, or yellow).
- Adjacent sections shall be interlocked together.
- Support device shall not extend beyond the detection plate into the pathway.
 - Barricades shall be used to close the entire width of the pathway.

Detectable Pedestrian Barricade/Channelizer



<u>Barricade</u>





*Optional during daylight hours (See general note #16)

Length and Device Spacing for Lane Closure

Speed Limit	Minimum Taper Length (L)***			Min. No. of Devices for Taper	Maximum Device Spacing
M.P.H.	Lane Width in Feet 10 11 12			(12FT. Lane)	In Feet
20 25 30 35 40 45 50 55	70 105 150 205 270 450 500 550	75 115 165 225 295 495 550 605	80 125 180 245 320 540 600 660	5 6 7 8 9 13 13	20 25 30 35 40 45 50 55

 $L = SxW \qquad S \ge 45 MPH$ $L = S^2xW/60 \qquad S \le 40 MPH$


- L = Minimum Taper Length (Feet)
 W = Width of Offset (Feet)
 S = Posted Speed Limits Prior to Construction (MPH)

Length of downstream taper to be between 50' and 100' with device spacing of 20'.

LEGEND

(Applies to the Following Traffic Control Detail Sheets)

CMS Changeable Message Sign




шш Detectable Pedestrian Barricade/Channelizer

Type 3 Barricade

+→Traffic or Pedestrian Signal

\\\Pavement Marking To Be Removed



- @ Sign Code
- → Sign Symbol
- Channelizing Device
- Flagger
- ₩ Arrow Board Support
- ⇒ Direction of Traffic
- ▶ Direction Indicator Barricade
- o Tubular Markers

Metcalf CLOSED NORTH OF 167th FOLLOW DETOUR

Legend and Border: Black Background: Orange Text Series: Uppercase: 6" Series C, Lowercase 4.5" Series C


2.25" Radius

1. All street names on special signs shall be upper and lower case letters. 2. The legend shown is a typical example. Modify the legend for specific purpose.

SPECIAL CONSTRUCTION SIGN DETAIL

FEMPORARY TRAFFIC CONTROI GENERAL NOTES & DETAILS

CITY OF OVERLAND PARK PARTMENT OF PUBLIC WORKS



Sign Designations

Subscript Codes

L - Left

R – Right

S — Straight AL — Advance Left AR — Advance Right

DL — Diagonal Left DR — Diagonal Right

<u>Notes</u>

Sizes shown are for conventional roadways.
 Signs (1), (2), and (3), shall be mounted on

48"x24" 60"x30" 96"x48"


Speed Limit \leq 30 MPH Speed Limit = 35, 40, 45 MPH Speed Limit \geq 50 MPH






Arrow board shall be set in the flashing caution mode for shoulder work, roadside work near the shoulder, or temporary closing of one lane on a two-lane, two-way roadway.

<u>Arrow Board</u>




Advance Warning Sign Spacing Table


D4 T	Minimum Distance Between Signs					
Road Type	Α	В	С	D		
Urban (Speed Limit ≤ 30 MPH)	100'	100'	100'	100'		
Urban (Speed Limit ≥ 35 MPH)	350'	350'	350'	150'		
Rural (Speed Limit ≤ 40 MPH)	350'	350'	350'	200'		
Rural (Speed Limit > 40 MPH)	500'	500'	500'	200'		



Note: * Applies to any subsequent sign in the work zone.



Top View



Side View

Temporary Sidewalk Detail

<u>Notes</u>

- 1. A temporary sidewalk may be installed, in lieu of providing a pedestrian detour, when removing sidewalk panels during construction with approval the Engineer.


 2. The temporary sidewalk shall be installed immediately after the sidewalk has been removed.


 3. As an alternative to the temporary boardwalk sidewalk, the contractor m to backfill with digable flowable fill up to the surface of the existing sidewalkins.


47 53

TEMPORARY TRAFFIC CONTROL SIGN & PLACEMENT DETAILS

CITY OF OVERLAND PARK DEPARTMENT OF PUBLIC WORKS







CITY OF OVERLAND PARK DEPARTMENT OF PUBLIC WORKS